

Customer Information

Sunrise Construction Ltd
 Mike Johnson
 125 King Street
 Toronto, Ontario, M5H 2Y5
 416-555-0123
 mjohnson@sunriseconstruction.com

Project Address

500 University Avenue
 Toronto, Ontario
 M5G 1V6

Concrete Summary

Type	Length	Thick	Sq Ft	Cu Ft	Cu Yd	m ³
Walls	219'-2.75"	-	1619.92	1349.93	50.00	38.23
Footings	-	-	-	439.28	16.27	12.44
Bearing Pad	Qty: 1: 48" × 48"	20"	16.00	26.67	0.99	0.7551
Bearing Pad	Qty: 1: 24" × 24"	10"	4.00	3.33	0.12	0.0944
Basement Floor	-	4"	879.28	293.09	10.86	8.30
Garage Floor	-	5"	378.13	157.55	5.84	4.46
Cold Room Floor	-	4"	136.79	45.60	1.69	1.29
Porch Floor	-	5"	180.43	75.18	2.78	2.13
Total	219'-2.75"	-	3194.54	2390.63	88.54	67.70

Height 8'

14 walls

Wall	Length	Tie	24"	22"	20"	18"	16"	14"	12"	10"	8"	6"	4"	Gap
1A	34' 5.5" (413.5")	10" 204 ties	16											1.5"
1B	32' 9.5" (393.5")		16											1.5"
2A	35' 5.5" (425.5")	10" 216 ties	17								1			1.5"
2B	35' 5.5" (425.5")		17								1			1.5"
3A	9' 1" (109")	10" 54 ties	3			1								1"
3B	8' 3" (99")		3			1								1"
4A	18' 7.5" (223.5")	10" 108 ties	8											3.5"
4B	16' 11.5" (203.5")		8											3.5"
5A	16' 10.25" (202.25")	10" 108 ties	8											2.3"
5B	16' 10.25" (202.25")		8											2.3"
6A	7' 1" (85")	10" 48 ties	2			1								1"
6B	5' 11" (71")		2			1								1"
7A	4' 0" (48")	10" 30 ties	1		1									
7B	4' 0" (48")		1		1									
10A	2' 6" (30")	10" 18 ties					1							
10B	1' 8" (20")						1							

Wall	Length	Tie	24"	22"	20"	18"	16"	14"	12"	10"	8"	6"	4"	Gap
11A	5' 0" (60")	10" 36 ties	1			1								
11B	3' 10" (46")		1			1								
12A	17' 7.5" (211.5")	10" 108 ties	8											1.5"
12B	16' 9.5" (201.5")		8											1.5"
13A	15' 10" (190")	10" 108 ties	7										1	
13B	14' 8" (176")		7										1	
14A	17' 10.25" (214.25")	10" 120 ties	8										1	0.3"
14B	16' 8.25" (200.25")		8										1	0.3"
15A	1' 2.25" (14.25")	10" 18 ties								1				0.3"
15B	0' 10.25" (10.25")									1				0.3"
16A	1' 2.25" (14.25")	10" 24 ties										1		0.3"
16B	0' 6.25" (6.25")											1		0.3"
Total			158		2	6	2			2	2	2	4	

Height 4'

2 walls

Wall	Length	Tie	24"	22"	20"	18"	16"	14"	12"	10"	8"	6"	4"	Gap
8A	16' 10" (202")	10" 51 ties	7		1									
8B	16' 0" (192")		7		1									
9A	16' 7.75" (199.75")	10" 51 ties	7				1							1.8"
9B	15' 9.75" (189.75")		7				1							1.8"
Total			28		2		2							